









CORESITE SV-4 DATA CENTER

PROJECT NARRATIVE


The ConXL System frame for this 100,000 ft² data center in Santa Clara, CA was erected in 9 working days. The building was designed to LEED Gold standards, featuring energy efficiency initiatives such as 97% efficient UPS units, variable frequency drive (VFD) cooling units, and air-side economization. The data center is part of CoreSite's 618,000 ft² campus at Coronado Drive and Stender Way.

CONX SOLUTIONS

The ConXL System addressed CoreSite's need for a robust, long-span steel data center frame delivered cost-effectively and with increased speed to market.

PROJECT DATA

| Square Footage | 100,000 ft ² |
|-------------------------|-----------------------------------|
| Steel Assembly Duration | 9 Days |
| Number of Collars | 64 |
| Bay Spacing | 28'-4" x 36" |
| Structure Weight | 622 tons; 13 lbs./ft ² |



STAKEHOLDERS

| Owner | CoreSite |
|------------------|--|
| Architect | DCM |
| Engineer | FBA Engineers |
| Contractor | MATT Construction |
| Steel Fabricator | ConXtech Manufacturing |
| Steel Erector | ConXtech Construction |
| ConXtech Scope | Structural Steel, Stairs, Metal Decking, Misc. Metals |

CONTACT US

ConXtech, Inc. 6701 Koll Center Parkway, Suite 150, Pleasanton, CA 94566 E-mail: info@conxtech.com | Phone: 510-264-9111 | www.ConXtech.com





